



Client: Holladay Construction Group
Contact: Mr. Tim Helton

Year: 2007
Project: AmeriPlex Phase V Wetland Mitigation
Project Type: Turnkey Construction

Williams Creek Management provided the specialty construction services required to build the wetland mitigation for Phase V of AmeriPlex, in Indianapolis, IN. Mitigation is required for projects with unavoidable impacts to wetlands and streams as part of the permitting process. The wetland mitigation has provided the opportunity for regional water quality improvement within the impaired waterway located within Phase V at AmeriPlex Indianapolis. Natural resource construction services provided include:

- Mass Earthwork and installation of agridrain
- Installation of 1,370 square feet of silt fence
- Installation of 206,091 square feet of high profile prairie seed mix
- Installation of 205,245 square feet of wetland understory seed mix
- Installation of 206,091 square feet of straw mulch
- Installation of 70 - 1 gallon native trees
- Installation of 335 - 1 gallon native shrubs



Construction



Post-Construction



Year One